Contract Title: RECESSED MONITOR WORK STATION, STATEWIDE CONTRACT

Contract Number: 406483

T-Number: 92464
Begin Date: 2006-04-01
End Date: 2007-03-31
Payment Terms: NONE
Delivery: 45 DAYS ARO
Political Subdivision Eligibility: Y

Master Ship-To: R0 (STATEWIDE DELIVERY)

Minimum Order: 0.00

Vendor Number: 37134393301 NOVA SOLUTIONS INC

PO BOX 725

EFFINGHAM, IL 62401

Vendor Contact: HENRY A KENTER Vendor Contact Phone: (800) 730-6682

Distributors?: Y Distributor Vendors:

Distributor Vendor Number: 37134393301 Region Code: R0 (STATEWIDE DELIVERY)

NOVA SOLUTIONS INC

PO BOX 725

EFFINGHAM, IL 62401

Vendor Contact: HENRY A KENTER Vendor Contact Phone: (800) 730-6682

Distributor Vendor Number: 37134393302 Region Code: R0 (STATEWIDE DELIVERY)

NOVA SOLUTIONS INC

LOUISIANA SCHOOL EQUIPMENT CO

3607 PERKINS RD STE B BATON ROUGE, LA 70808 Vendor Contact: KIM ASHTON

Vendor Contact Phone: (800) 730-6682 ext: 0246

## Contract Notes:

THIS CONTRACT IS WITH NOVA SOLUTIONS INC. ALL PAYMENTS ARE TO BE PROCESSED TO

371343933 01 NOVA SOLUTIONS INC. 421 WEST INDUSTRIAL AVE. P.O. BOX 725 EFFINGHAM, IL 62401

ORDERS MAY BE MAILED TO
371343933 02
NOVA SOLUTIONS INC.
LA. SCHOOL EQUIPMENT CO. LLC
3607 PERKINS ROAD SUITE B
BATON ROUGE, LA 70808
TEL 800-962-5732
FAX 337-988-6425

THIS IS A NON-MANDATORY CONTRACT.

NORMAL DELIVERY IS 4 WEEKS.

NOVA SOLUTIONS OFFERS A QUICK SHIP PROGRAM ON THE FOLLOWING MODEL

NUMBERS AND LAMINATE CHOICES THAT WILL SHIP WITHIN TEN (10) DAYS FROM RECIEPT OF ORDER.

45-0-0012, 45-0-0011, 45-0-0022, 45-0-0021, 45-SA-0012, 45-0-SA0011 45-0-SA-0022 AND 45-0-SA0021.

THE BASE SELECTION AVAILABLE IS BLACK, FASHION GRAY, FUSION MAPLE, TOP SELECTION IS FASHION GREY, GREY NEBULA, FUSION MAPLE, WILD CHERRY

SUBSTITUTIONS/DISCONTINUED ITEMS; ONLY THE BRAND AND PRODUCT NUMBERS LISTED ARE APPROVED FOR SHIPMENT. ANY SUBSTITUTIONS MUST RECEIVE PRIOR APPROVAL FROM THE OFFICE OF STATE PURCHASING. THE VENDOR SHALL NOTIFY OFFICE OF STATE PURCHASING OF ANY APPROVED NUMBERS THAT HAS BEEN DISCONTINUED.

THE OFFICE OF STATE PURCHASING IS THE SOLE AUTHORITY IN ANY CHANGES MODIFICATIONS, ADMENDMENTS, ALTERATIONS, CLARIFICATIONS, PRICES. SPECIFICATIONS, TERMS AND CONDITIONS OF THE CONTRACT.

## RECESSED MONITOR WORKSTATION SPECIFICATIONS:

WORKSTATION WILL BE A RECESSED MONITOR DESK AND WILL BE DESIGNED TO SUPPORT THE MONITOR BELOW A GLASS SURFACE. ALL WORKSTATIONS SHOULD HAVE A THEMOFUSED LAMINATE TOP. THE WORK-SURFACE THICKNESS IS TO BE A MINIMUM OF 1-1/8" THICK. THE WORKSTATION'S BASE COMPONENTS SHOULD BE MANUFACTURED WITH THEMOFUSED LAMINATE. THE BASE THICKNESS IS TO BE A MINIMUM OF  $\frac{1}{2}$ " THICK

THE WORKSTATION'S GLASS SIZE IS TO BE A MINIMUM OF 18" W X 21" D. THE GLASS MUST BE OF HIGH QUALITY AND IS TO BE TINTED AND TEMPERED. THE GLASS THICKNESS IS TO BE A MINIMUM OF 3/16" THICK.

A FULL SIZE MONITOR IS TO BE ADJUSTABLE BETWEEN 20 AND 40 DEGREES. FLAT PANEL MONITOR ARE TO BE ATTACHED TO AN ADAPTER ARM USING THE INDUSTRY STANDARD VESA BOLT PATTERN.

THE WORKSTATION'S WIRE MANAGEMENT SYSTEM IS LOCATED IN THE REAR OF THE UNIT. EACH UNIT IS FURNISHED WITH STANDARD SIZE GROMMETS LOCATED ON BOTH THE LEFT AND RIGHT END PANEL AND HAVE A STANDARD GROMMET ON THE WORK-SURFACE.

THE WORKSTATIONS ARE FURNISHED WITH AN ACCESS PANEL LOCATED ON THE BACK OF THE UNIT. THE ACCESS PANEL RUNS THE FULL LENGTH OF THE UNIT.

THE WORKSTATION'S POWER SYSTEM INCLUDES A (6) OUTLET 15 AMP MULTI-PLUG OUTLET WITH REMOTE ON/OFF SWITCH AND 10FT CORD.

IN ORDER TO ACCOMMODATE BOTH RIGHT-HANDED AND LEFT-HANDED USERS, MONITOR POSITIONS ARE AVAILABLE WITH EITHER A LEFT OR RIGHT VIEWPORT.

THE WORKSTATIONS ARE FURNISHED WITH A FULL LENGTH PULL OUT KEYBOARD TRAY WITH ENOUGH ROOM FOR USING A STANDARD MOUSE.

THE WORKSTATIONS ARE FURNISHED WITH A VISOR TO OFFER ADDITIONAL GLARE PROTECTION FOR UNUSUAL LIGHTING CONDITIONS.

THE WORKSTATIONS ARE FURNISHED WITH ADJUSTABLE LEVELERS. THE LEVELERS ARE FITTED INTO A METAL INSERT.

THE WORKSTATIONS ARE FURNISHED WITH LAMINATED CPU SHELVES TO HOUSE THE MONITOR.

TECHNICAL ASSISTANCE SUCH AS ANALYSIS AND SPACE PLANNING, CAD DRAWINGS AND LAYOUT DRAWINGS ARE INCLUDED IN THE SCOPE OF SERVICE UNDER THIS CONTRACT AT NO ADDITIONAL CHARGE.

LAMINATE WORK SURFACE COLORS ARE AVAILABLE IN 33 COLORS. BASE COMPONANT AVAILABLE IN 25 COLORS.

BASIC INSTALLATION SERVICES (AT NO ADDITIONAL COST) SHALL INCLUDE:

THE VENDOR IS RESPONSIBLE FOR UNLOADING THE FURNITURE FROM THE TRUCK, FULLY ASSEMBLING, (EXCLUDING THE CPUS, MONITORS, AND KEYBOARDS AND MOUSE DEVICES), PLACING EACH WORKSTATION IN DESIGNATED AREA(S) AT THE DISCRETION OF THE END USER, AND DISCARDING ALL ASSOCIATED DEBRIS OFF PREMISES.

THE VENDOR SHALL INSPECT THE FURNITURE FOR ANY OBVIOUS DAMAGE AND PROPERLY DOCUMENT THE DELIVERY TICKET

THE VENDOR SHALL PROVIDE ON-SITE TRAINING TO THE END USER IN THE PROPER INSTALLATION AND ADJUSTMENT OF ONE OF THE MONITORS INTO THE THE WORKSTATION IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS.

OPTIONAL INSTALLATION SERVICES (AT AN ADDITIONAL COST) SHALL INCLUDE:

THE INSTALLATION OF ALL CPU'S, MONITORS, KEYBOARDS AND MOUSE DEVICES IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS. CONNECTIVITY, CABLING AND HARD WIRE ELECTRICAL SERVICES ARE NOT INCLUDED.

SEE LINE 00011 FOR CHARGES FOR THESE ADDITIONAL SERVICES.

Contract Items:

Line# Commodity# Unit Price UoM Brand Model

00001 42518120334 367.82000 EACH NOVA SOLUTIONS

45-0-0012

45-0-0011

45-0-0022

WORKSTATION, 30" DEEP X 30" WIDE X 30" HIGH DESK TO ACCOMMODATE FULL SIZE CRT MONITOR WITH MAXIMUM MONITOR DIMENSIONS OF 17" WIDE X 17 1/2" DEEP X 18" HIGH. VIEW-PORT LEFT, CPU RIGHT.

00002 42518120335 367.82000 EACH NOVA SOLUTIONS

WORKSTATION, 30" DEEP X 30" WIDE X 30" HIGH DESK TO ACCOMMODATE FULL SIZE CRT MONITOR WITH MAXIMUM MONITOR DIMENSIONS OF 17" WIDE X 17 1/2" DEEP X 18" HIGH. VIEW-PORT RIGHT, CPU LEFT.

00003 42518120336 392.73000 EACH NOVA SOLUTIONS

WORKSTATION, 30" DEEP X 36" WIDE X 30" HIGH DESK TO ACCOMMODATE FULL SIZE CRT MONITOR WITH MAXIMUM MONITOR DIMENSIONS OF 17" WIDE X 17 1/2" DEEP X 18" HIGH. VIEW-PORT LEFT, CPU RIGHT.

00004 42518120337 392.73000 EACH NOVA SOLUTIONS WORKSTATION, 30" DEEP X 36" WIDE X 30" 45-0-0021

HIGH DESK TO ACCOMMODATE FULL SIZE CRT MONITOR WITH MAXIMUM MONITOR DIMENSIONS OF 17" WIDE X 17 1/2" DEEP X 18" HIGH. VIEW-PORT RIGHT, CPU LEFT.

00005	WORKSTATION, 30" DEEP X 72" WIDE X 30" HIGH DESK TO ACCOMMODATE (2) FULL SIZE CRT MONITORS WITH MAXIMUM MONITOR DIMENSIONS OF 17" WIDE X 17 1/2" DEEP X 18" HIGH. VIEW-PORT LEFT AND RIGHT WITH CENTER CPU STORAGE.	42518120338	876.09000	EACH	NOVA SOLUTIONS 45-0-0700
00006	WORKSTATION, 30" DEEP X 30" WIDE X 30" HIGH DESK TO ACCOMMODATE A FLAT PANEL MONITOR USING A FLAT PANEL ARM/VESA BRACKET. MONITOR DIMENSION NOT TO EXCEED 17" WIDE X 18" HIGH. VIEW-PORT LEFT, CPU RIGHT.	42518120339	367.82000	EACH	NOVA SOLUTIONS 45-0-SA0012
00007	WORKSTATION, 30" DEEP X 30" WIDE X 30" HIGH DESK TO ACCOMMODATE A FLAT PANEL MONITOR USING A FLAT PANEL ARM/VESA BRACKET. MONITOR DIMENSION NOT TO EXCEED 17" WIDE X 18" HIGH. VIEW-PORT RIGHT, CPU LEFT.	42518120340	367.82000	EACH	NOVA SOLUTIONS 45-0-SA0011
00008	WORKSTATION, 30" DEEP X 36" WIDE X 30" HIGH DESK TO ACCOMMODATE A FLAT PANEL MONITOR USING A FLAT PANEL ARM/VESA BRACKET. MONITOR DIMENSION NOT TO EXCEED 17" WIDE X 18" HIGH. VIEW-PORT LEFT, CPU RIGHT.	42518120341	392.73000	EACH	NOVA SOLUTIONS 45-0-SA0022
00009	WORKSTATION, 30" DEEP X 30" WIDE X 30" HIGH DESK TO ACCOMMODATE A FLAT PANEL MONITOR USING A FLAT PANEL ARM/VESA BRACKET. MONITOR DIMENSION NOT TO EXCEED 17" WIDE X 18" HIGH. VIEW-PORT LEFT, CPU RIGHT.	42518120342	392.73000	EACH	NOVA SOLUTIONS 45-0-SA0021
00010	WORKSTATION, 30" DEEP X 72" WIDE X 30" HIGH TO ACCOMMODATE (2) FLAT PANEL MONITORS USING A FLAT PANEL ARM/VESA BRACKET. MAXIMUM MONITOR DIMENSIONS OF 17" WIDE X 18" HIGH. VIEW-PORT LEFT AND RIGHT WITH CENTER CPU STORAGE.	42518120343	876.09000	EACH	NOVA SOLUTIONS 45-0-SA0700
00011	OPTIONAL INSTALLATION CHARGE: INSTALLATION SERVICES OF TWO OR MORE MONITORS, CPU, KEYBOARDS IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS. APPLICABLE WHEN DELIVERED TO SAME LOCATION AND SINGLE SHIPMENT. THE CHARGE IS PER WORKSTATION	96246120411	5.77000	EACH	NOVA SOLUTIONS INSTALLATION

CHARGE IS PER WORKSTATION.



## **Laminate Color Selections**







